

**SURVEY &
REMONUMENTATION**

2026

OCT 05 1998

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
SECTION Filing Requirement of Act 74, Mich. P.A. 1970

20 APR 98 2:19 P.M.

For corners in

Roscommon
(County)

Located In:

Corner Code #

ROBERT W. SMITH
REGISTER OF DEEDS

1. Public Land Survey	T <u>24N</u> R <u>1W</u>	<u>L-13</u>
	T <u>23N</u> R <u>1W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

To be filed in Liber 3 of Land Corners

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on March 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-13	G.L.O - 1838 Lewis Clason, DS Mon. - Post 10' W. Pine N53°E 15 lks. 7' Spruce N65°W 22 lks.	1900's Marcus Schaeff Michigan Dept. of Conservation Mon: Found or established, and replaced	L 2, Pg. 465 Mon. - Axle Shaft in Center Line N-S Road 5' Tamarack N66°W 93.7' 6' Tamarack N22°E 90.4'
	L 1, Pg. 101 (Herbert L. Fluharty, P.S. #18223 9-11-1974) Mon. - Found Gear Shaft in Center Line Co. Rd. 600 P.P. N75°W 43.80' 5' Poplar N50°E 50.69' 9' Beisem N30°E 90.45'	L 1, Pg. 155 (Frank J. Arleth P.S. #2126 April 2, 1975) Mon. - Found 1 1/4" Axle Shaft Nails in: P. Pole N80°W 43.8' 6' Tamarack N30°E 90.5'	ROSCOMMON COUNTY PEER GROUP APPROVAL DATE <u>MARCH 27 1998</u> <i>Marvin E. Myers MPEM</i> Marvin E. Myers, P.S. County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1 1/4" axle shaft in Monument box in the centerline of F97 (St. Helan Road) and 200'± South of the centerline of Marl Lake Road
Found spike in Southwest face Power Pole N72°W 43.90'
No other accessories were found. Accepted as the best available evidence of the position of the Original Corner.
Replaced 1 1/4" x 36" axle shaft with standard Roscommon County monument in monument box in centerline of F-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Standard Roscommon County Monument in monument box.
Wit: Set carsonite post 33' East.
Found spike in Southwest face Power Pole N72°W 43.90'
Set nail & tag in Southeast face 8" Poplar N52°E 50.43'
Face of highway R.O.W. marker S50°E 41.49'
Set nail & tag in Southwest face 10" Tamarack S19°E 101.45'



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date April 10, 1998

LIBER 3 PAGE 499