

92533 1 9 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 28 10 47 AM '93

COMMISSION

For corners in  
Roscommon  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 23 R 1 W I - 9
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-14-93

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

William Burt Set Pos 1852  
S. Pine 5" N19½°W 9 Lks  
S. Pine 7" S67°E 14 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Southwest corner of Section 23 was found ½" bar bent over pipe which was set by Henning 1947, said corner in Pav't Box. All witnesses destroyed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Std. Mon Stamped I - 9  
in pav't box  
Nail & tag P. Pole S60°W 65.53 M. D. O.T. witness tag  
Nail & tag P. Pole S32°E 54.60  
Nail & tag P. Pole S68°E 116.94  
Top of bolt of inspection plate on Northeast side of metal light pole N50°W 52.20



Signed by Frank J. Arleth Date 21 DEC 93  
Surveyor's Michigan License No. 21266

Date December 14, 1993 Peer Group Approved