

8382 SURVEY & REMONUMENTATION

APR 24 1995

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------|---------------|
| Roscommon (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T <u>23</u> R <u>1</u> W | I -10 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

15 NOV 24 9:12 A.M.

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 William Burt set post 1852
 S. pine 8" S13 W 19°1ks
 S. pine 5" N50 E 25°Lks
 Delamater set 1/2" x 18" bar for corner 1929.
 R.C.R.C. Wit: M.D.O.T. tags
 P. Pole S89°E 74.30
 P. pole S88°W 57.50
 Ostline & Henning 1949 Found 1/2" bar in centerling of M-76 WIT: 6" J. pine S43°30 E 65.1 destroyed
 6" J. pine S47°W 67.3
 Corner recorded by Ostline for Sutherby Sub-1952, L. 3 P. 53
 Corner recorded by Henning for Plat of Pinewood Hill 1946 L. 3 P. 7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 November 1994 Arleth found 1/2" bar in pav't box in centerline of M-76.
 Found concrete monument 60' East
 Found M.D.O.T. N & T in witness still OK
 P. Pole S89°E 74.30
 P. Pole S88°W 57.50

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Roscommon County standard monument I-10 in Pav't Box
 N & T 18" N. pine S81°E 110.0
 N & T P. pole S36°E 124.10
 N & T 24" N. pine S41°30'E 144.40
 M. D. O. T. tag P. pole S89°E 74.30
 M. D. O. T. tag P. pole S88°W 44.0
 Set carsonite survey post S88°W 44.0



Signed by Frank J. Arleth Date 11/11/94
 Surveyor's Michigan License No. 21266 P.S.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

DATE 11/10/94 Peer Group Approved LIBER 3 PAGE 162