

# SURVEY & REMONUMENTATION

ROSCOMMON COUNTY REMONUMENTATION  
**APR 24 1995**  
**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

15 APR 1995 9:55 A.M.

For corners in  
Roscommon  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>23</u> R <u>1</u> W	<u>I - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TO BE FILED IN LIBER 3 OF LAND CORNERS  
**Register of Deeds Stamp & File Number**

I, Frank J. Arleth, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

William Burt set post 1852	Henning & Ostline 1944 found 1" pipe.
S. pine 6" N69°E 15 Lks	Wit; BT 7" J. pine N38°E 82.5
S. pine 7" S45°W 19 lks	BT 7" J. pine S54°E 50.2
Delamater set 1" x 24" pipe	R.C.R.C. found 1" pipe in pav't box centerline of
Centerline of M-76 1929.	Artesia beach road west and M-76.
No. witness	Wit; 7" J. pine N38°E 82.5
	7" J. pine S54°E 50.2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 1994 Arleth found 1" pipe in pav't box.	M. S. H. D. Wit:
Henning Wit. destroyed	N & T p. pole S65°W 76.80
	N & T p. pole N60°E 77.45
	N & T 10" J. pine N55°W 71.50

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Standard monument in pav't box I-11

N & T 8" N. pine S56°30'E 61.40


N & T 8" J. pine N44°E 77.00

M. O. D. T. N & T p. pole S65°W 76.80

M. O. D. T. N & T 10" J. pine N55°W 71.50

M. O. D. T. p. pole N60°E 77.45'

Set carsonite survey post N55°W 61.50



Signed by Frank J. Arleth Date 11/11/94  
 Surveyor's Michigan License No. 21266 P.S.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

DATE 11/10/94 Peer Group Approved  
**LIBER 3 PAGE 163**