

FEB 19 1993

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON
REC 1993

9254

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 47 AM '93

For corners in

Roscommon
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 23 R 1 W J - 7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Robert J. Arleth
REGISTERED SURVEYOR

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

William Burt set post 1852
Y. Pine 12" S87°E 19 Lks
Y. Pine 15" N52°W 63 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete Mon., Corner is the Northwest corner of the Plat of CEDAR LAKE SUBDIVISION NO. 4, (2/1/63)
Cavanagh witness 1977 all in place
16" J. Pine S35°E 53.3
16" J. Pine N17°30'E 51.6 (stump as of 1993)
5" W. Pine S20°W 14.35 (10" W. Pine as of 1993)
Henning W. Pine stump S40°W 92.0 1954 survey

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Used concrete Mon. with cap 21266
Nail & tag in 6" W. pine N43°W 45.25
Nail & tag in 10 Twin maple S44°W 36.15
Nail & tag in 8" W. Pine S47°E 24.37
Nail & tag in 7" Maple N38°E 21.83
Set carsonite Post 2.0 Northwest of corner



Signed by *Frank J. Arleth*

Date 22 DEC 93

Surveyor's Michigan License No. 21266

Date December 14, 1993

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983