

ROSCOMMON COUNTY REMONUMENTATION

FEB 18 1994
9255
COMMERCIAL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 47 AM '93

For corners in

Roscommon
(County)

Located in:

Corner Code #

- | | | | | | | |
|------------------------------------|---|----|---|---|---|-------|
| 1. Public Land Survey | T | 23 | R | 1 | W | J - 9 |
| | T | | R | | | |
| | T | | R | | | |
| | T | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | |
| | S | | T | | R | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | |
| | S | | T | | R | |

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

William Burt set post 1852
S. Pine 6" S7°W 12 Lks.
S. Pine 5" N12°E 35 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

South 1/4 corner of Section 23, T23N, R1W, found pav't no corner in box.
Witness by Cavanagh intersect in center of pav't box, Cavanagh found concrete mon. in 1977
R.C.R.C. road construction destroyed concrete mon. Corner is the NE corner of Veldora subdivision -(9/17/62)
Witness: Nail in P. Pole South 31.02
Nail in P. Pole N70°W 78.0
NBT 12" J. Pine N35°E 56.65
1/2" bar 33.0 North
concrete mon 33.0 South

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Std. Mon. - stamped J - 9
Nail & tag 10" B. Oak S49°E 58.26
Nail & tag 7" J. Pine N47°E 56.80
Nail & tag 6" J. Pine S62°W 71.27
Nail & tag Power pole N64°W 77.90
1/2" bar 33.0 North
Concrete mon. 33.0 South



Signed by Frank J. Arleth
Surveyor's Michigan License No. 21266

Date 22 DEC 93

Date December 14, 1993 Peer Group Approved