

9258

FEB 16 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF ROSCOMMON

DEC 28 10 47 AM '93

For corners in  
Roscommon  
(County)

Located in: Corner Code #

- 1. Public Land Survey T 23 R 1 W K - 9
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

REGISTRE

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-14-93

Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- William Burt Set Post 1852
- S. Pine 8" N17°W 23 Lks.
- S. Pine 6" S49°E 24 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- S.E. corner of Section 23, T23N, R1W, found Pav't box, 10" log spike above concrete Mon. in pav't box. In 1991 Arleth Land Survey Company found concrete mon.
- Wit: 16" B. Oak N50°W 49.6'
- 8" J. Pine N41°E 67.35
- 12" J. Pine S18°W 72.10
- Concrete Mon was placed when plat of East St. Helen was made 8/5/46

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1.0 foot of Roscommon County Std. Mon over concrete mon in pav't box, stamped K - 9
- Nail & tag in 10" B. Oak N36°W 87.35
- Nail & tag in 18" N. Pine S31°E 91.60
- Nail & tag in 18" N. Pine N52°E 61.64
- Nail & tag in power pole S43°W 46.28

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
6												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by Frank J. Arleth  
Surveyor's Michigan License No. 21266  
Date December 14, 1993

Date 22 DEC 93

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

