

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>24</u> N. <u>1</u> E. <u>1</u> W. <u>1</u>	<u>K-10</u>
2. PROPERTY CONTROLLING IN SECTION <u>26</u>	T. <u>24</u> N. <u>1</u> E. <u>1</u> W. <u>1</u>	<u>13</u> <u>12</u> <u>&lt;</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl R. Johnson, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 15, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-10 - Set corner at found 1 1/4" pipe in concrete centerline of road N-S.
- 13 - Set 1/2" bar by Henning 0.94' north of present location to comply with found E 1/4 corner of section.
- 12 - Set 1/2" bar by Henning 0.79' north of present position to comply with found E 1/4 corner of section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K-10</u>	<u>13</u>	<u>12</u>
Set DNR mon at fd 1 1/4" pipe in concrete	Set 1/2" bar & cedar post	Set 1/2" bar & cedar post
14" Red Oak N74°E 24.7'	6" Red Oak N46°W 37.2'	9" White Birch N42°E 47.0'
8" Red Oak S62°W 38.9'	8" Red Oak N66°E 4.8'	9" Red Oak N63°W 28.7'
Cedar Post w/loc tag N89°W 10.0'		

SIGNED BY \_\_\_\_\_

*Carl R. Johnson*

DATE 4/3/86

SURVEYOR'S MICHIGAN REGISTRATION NO. 30083

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_


CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

ROSCOMMON COUNTY