

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Roscommon</u> (County)	Located In	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S 16 T 24N R 01W	8	
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Carl T. Kiiskila, in a field survey on January 5, 2011 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

8- CW 1/16 corner, section 16, T24N, R01W

None

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

8- CW 1/16 corner, section 16, T24N, R01W

Found 1/2"x 48" rebar not of record. Iron fits within 1' of calculated position for corner. Accepted found iron as the best available evidence for the position of the corner. Replaced found iron with a stamped 2" dia. aluminum cap on 5/8"x 34" rebar. Found no other evidence to dispute the location for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8- CW 1/16 corner, section 16, T24N, R01W

2" dia. stamped aluminum cap on 5/8"x34" rebar.

Wit: N20°E 36.87' to set N&T on W side 12" W. Pine
 S06°E 13.68' to set N&T on SW side 12" R. Pine
 S50°W 53.00' to set N&T on NW side 13" S. Maple
 N24°W 49.26' to set N&T on W side 10" W. Pine
 Set Blue Carsonite Post w/ loc. tag 1' North



Carl T. Kiiskila

6-1-11

Surveyor's Michigan License No.: 33981