

9556

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAY 28 1997

COMMISSION

For corners in Roscommon

(County)

Located In:

Corner Code #

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

23 DEC 96 9:48 A.M.

ROBERT W. SMITH

Register of Deeds Stamp & File Number

Table with 5 rows and 4 columns: 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Section, 4. Lot No., 5. Private Claims. Columns include T, R, M, A codes and values.

Grid table with columns A-L and rows 2-13. Contains numerical values in each cell.

I, Marvin E. Myers, in a field survey on November, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO William Burt June 9, 1852 Mon.-Post WIT: 9" Aspen N27°E 75 lks. 8" Aspen N07°W 67 lks.
G.D. Henning Oct. 30 1946 Mon.-Iron Bar WIT: US 1937 wit. cor. N50°E 44.9'
G.D. Henning Feb. 6, 1977 L.168, pg.127 (Crawford County) Mon.-Fd. 1/2" bar in pav't box WIT: 1/2" bar N46°29'W 46.98' Conc. mon. S29°21'W 68.9'
US GLO G. Veal 1937 Mon.-Accepted intersection of roads as best available evidence. Set 6" dia. x 12" long concrete block to mark corner.
R.T. Ostling July 1959 L.4 of plats, pg. 32 DEERHEART WOODS ANNEX Mon.-MSHD pav't box
WIT: Set witness monument 24" long x 12" dia. at base & 8" dia. at tip with 3 1/2" dia Brass Tablet N50°E 68 lks. from which the following were taken: 12" B.Oak S41 1/2°W 131 lks. 10" B.Oak N86 1/2°W 179 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box with 3/4" Iron Bar inside. Found accessories 1/2" Bar N46°W 46.98 feet and concrete monument S29°W 68.84 feet and accepted as the best available evidence of the position of the Original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard Crawford County Monument in pav't box
WIT: 8" W.Pine N30°E 60.78'
6" W.Pine N20°W 77.00'
Conc. mon. S35°W 68.84'
4" W.Pine S40°E 56.62'
1/2" Bar N46°29'W 46.98'
Monument is at intersection of roads



ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE NOV 22, 1996

Signature of Marvin E. Myers, P.S.
Marvin E. Myers, P.S.
County Surveyor

Signed by [Signature]

Date December 13, 1996

Surveyor's Michigan License No. 31600

11850 3 DATE 347