

4629

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in  
Roscommon County

11 JUL 97 4:12 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

	Located in:	Corner Code #
1. Public Land Survey	T23N R2W	M-1
	T24N R2W	M-13
	T24N R1W	A-13 ✓
	T23N R1W	A-1

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

SET POST WILLIAM BURT 1852  
WIT: BIRCH 6 S73W 7 LKS  
BIRCH 6 N56E 21 LKS

LCRC LIBER 2, PAGE 503  
2" IRON PIPE & 4"X4" STAKE  
WIT: 5" POPLAR N5°W 41.09'  
8" POPLAR S83°E 77.02'  
3" POPLAR S47°E 31.34'

M.D.S. HIGHWAY 1948  
WITNESSES TO TWP. COR.  
SE COR. OF SEC. 36, T24N, R2W  
2" IRON PIPE & 4" SQ. STAKE  
N5°W 41.09' - 5" POPLAR  
S83°E 70.02' - 8" POPLAR  
S47°E 31.34' - 3" POPLAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" PIPE (O.D.) POSSIBLY AS SET BY SCHAAF  
5" POPLAR N5°W 41.09'  
8" POPLAR S83°E 77.02'  
3" POPLAR S47°E 31.34'  
NOTE: GLO CALLS TO LEAVE SWAMP 4 CHAINS WEST OF CORNER AT 262' WEST OF PIPE, WE LEAVE A TAG ALDER SWAMP AND ENTER A STAND OF SPRUCE AND ASPEN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT #17614 1997  
WIT: NAIL & TAG IN 10" POPLAR S78°W 17.58'  
NAIL & TAG IN 4" POPLAR S27°E 12.01'  
NAIL & TAG IN 8" POPLAR S25°W 10.42'  
NAIL & TAG IN 10" POPLAR N75°E 7.78'  
CARSONITE POST NORTH 2'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &  
REMONUMENTATION

APR 07 1998

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE July 8, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 422