

7867

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon
(County)

Located in:

Corner Code #

30 OCT 97 12:29 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Table with 3 columns: Description, T/R, Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section.

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No.
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked at row 7, column B.

I, Marvin E. Myers, in a field survey on August, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 Wm. Burt, D.S.
Mon. - Post
WIT: 6" W.Pine N86°W 6 lks.
6" W.Pine S79°E 8 lks.
8" W.Pine N87°46'W 135 lks.
Feb. 24, 1989 F.J. Arleth
Mon.-Fd. 1/2" Bar
WIT: 12" B.Oak S14°W 41.55'
8" R.Pine N50°W 23.90'
5" W.Pine N84°E 33.30'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Oct 2, 1997
MEW

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar & cap #17614 in 4" diameter pipe x 2.5' replaced with Standard County Mon. Fence going North & West
Accepted as best available evidence of the position of the original corner.


SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Monument
WIT: Nail & tag in S. side 4" B.Oak S58°E 28.19'
Nail & tag in E. face 8" Poplar S18°W 34.58'
Nail & tag in NW face 5" Poplar N32°E 24.93'
Nail & tag in S. face 18" R.Pine N70°W 20.33'
Fence North & West



Signed by Marvin E. Myers

Date Oct. 24, 1997

Surveyor's Michigan License No. 31600

LIBER 3 PAGE 424