

2910

SURVEY & REMONUMENTATION

OCT 05 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Roscommon  
(County)

Located In:

Corner Code #

- 1. Public Land Survey  
T 24N R 1W B-13  
T 23N R 1W B-1  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_
- 2. Property Controlling in Section  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec.  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

20 APR 98 2:17 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

To be filed in Liber 3 of Land Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on March 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838 Lewis Clason, DS	Michigan Department of Transportation
Mon. - Post	1958, M-76 Highway Plans, Project #72-28, Sheet 81
10" Birch N06°W 37 links	Mon: no description provided.
24" White Pine N36°E 27 links	Wit: Section line centerline distance provided (1373.0')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2"x36" pipe 1' below surface in east shoulder of Moore Road. Accepted as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument.

Wit: Set carsonite post 35' West.

- Set nail & tag in North face 10" Jack Pine N88°W 51.78'
- Set nail & tag in South face 6" Jack Pine N47W 52.89'
- Set nail & tag in Northwest face 8" Jack Pine N58°E 56.22'
- Set nail & tag in West face 8" Jack Pine South 70.90'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MARCH 27<sup>th</sup> 1998



Signed by Marvin E. Myers  
Marvin E. Myers, P.S.  
County Surveyor  
Surveyor's Michigan License No. 31600

Date April 10, 1998

LIBER 3 PAGE 492