

9558

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Roscommon
(County)

Located In:

Corner Code #

- | | | | | | |
|---|---|------------|---|-----------|--------------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>1W</u> | <u>C - 1</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous
Property in Section | S | | T | | |
| | S | | T | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

23 DEC 96 9:48 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on November, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-May 1839 John Brink
Mon.-Post
WIT: 8" Synn N50°E 33 lks.
8" Synn N40°W 22 lks.

R.T. Ostling May 22, 1956
Mon.-MSHD mon. box
WIT: 8' N of G W road
½" bar S 41'

F.J. Arieth
L.365, pg.323
Mon.-Pav't box
WIT: None given

GLO June 1852 William Burt
WIT: 6" Synn S45°E 9 lks.
8" Synn S50°W 38 lks.

Feldhauser July 7, 1970
Mon.-Mon. Box
WIT: Iron set South 33.0'

L.2, pg.436
Mon.-Pav't box

US GLO G. Veal 1937
Mon.-Accepted intersection of roads as the best available evidence of the position of the original corner. Set 10" long by 6" dia. concrete to mark corner
WIT: Set a 6" dia. x 24" long concrete witness monument with 3½" Brass Tablet N45°W 71 lks.

G.D. Henning Aug. 24, 1973
L.279, pg.544
Mon.-Pav't box in section corner
8' N of G road
WIT: Set by Highway Dept. from US Survey in 1937

L.2, pg.437
Mon.-Pav't box

G.D. Henning Nov. 9, 1948
Mon.-
WIT: Set pipe 33' South of corner

G.D. Henning Aug. 26, 1983
L.436, pg.327
Mon.-Not given
WIT: 1.34' S of G of M-18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box found 1" Iron Bar inside
Found 1" iron bar
Found ½" Bar 33.0' South
1.3' South of East - West centerline
7' East of centerline road North on fence line South
This position is accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced ½" bar with Standard Crawford County Monument in monument box.
WIT: Flooter Rd. sign post N24°E 54.92'
P.P. East face N14°W 98.72'
P.P. West face S06°E 38.38'
½" Iron Bar S03°W 33.06'

ROSCOMMON COUNTY

PEER GROUP APPROVAL

DATE NOV 8 1996

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers

Date December 13, 1996

Surveyor's Michigan License No. 31600