

2020

SURVEY & REMONUMENTATION

OCT 05 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon  
(County)

Located In:

Corner Code #

SECTION

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

20 APR 98 2:18 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

To be filed in Liber 3 of Land  
Corners

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 24N R 1W C-13  
T 23N R 1W C-1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on March 2, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1838 Lewis Claon, DS
- Mon. - Post
- 7" Beech N59 1/2°E 30 links
- 8" Beech N27 1/2°W 31 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2"x48" pipe broken off at ground surface.  
Accepted as the best available evidence of the position of the Original Corner.  
Replaced pipe with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument.  
Wit: Set carsonite post 1' South.  
Set nail & tag in West face 4" Oak S07°E 33.14'  
Set nail & tag in South face 8" White Pine N77°W 80.99'  
Set nail & tag in West face 4" Oak N06°E 61.51'  
Set nail & tag in West face 5" Oak N54°E 69.39'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MARCH 27<sup>th</sup> 1998  
*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date April 10, 1998

LIBER 3 PAGE 493