

**SURVEY &
REMONUMENTATION**

MAY 28 1997

9559

**COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	24N	R	1W	D - 1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

23 DEC 96 9:48 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on November, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO John Brink May 1839
Mon.-Post
WIT: 4" W.Pine N16°E 21 lks.
10" Aspen N40°W 60 lks.

US GLO Guy Veal 1937
Mon.-Accepted intersection of roads as best available position of original corner.
Set 10" long x 6" dia. concrete block to mark corner.
WIT: Set witness corner 24"x6" dia. with 3" Brass Tablet N50°E 70 lks.

L.2, pg.436
Mon.-1 1/2" pipe with 1/2"x24"
Bar in mon. box by intersection of Co. Road 602 & Old 144
WIT: 12" Elm N20°W 90.67'
9" N.Pine N45°W 79.60'
8" Maple N70°W 67.80'
R.T. Ostling May 15, 1962
Mon.-Fd. pipe
WIT: 8" Maple N26°W 67.9'
12" Elm N73°W 90.9'
8" N.Pine N35°W 79.7'
1/2"x24" Bar South 33.0'

G.D. Henning Aug. 24, 1973
L.279, pg.544
Mon.-Pipe in corner 4' N of C road
US Survey 1937
WIT: 8" Maple N26°W 67.9'
12" Elm N73°W 90.9'
8" Norway N55°W 79.7'
Henning 1958

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found old water valve with axle shaft for corner at intersection of road on fence line South
Found 1/2" Bar South 33.0 feet
Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced old water valve with monument box with Standard Crawford County monument
WIT: Nail & tag in 6" W.Pine N60°E 83.31'
Nail & tag in Stop Sign Post East edge N27°W 42.37'
Nail & tag in Fence Post S05°W 33.82'
Nail & tag in Sign Post West edge S20°W 23.99'

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE NOV 22 1996

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**



Signed by _____
Surveyor's Michigan License No. _____

Date Dec 13, 1996