

7869

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Roscommon (County)

Located In:

Corner Code #

- 1. Public Land Survey T 24N R 1W D - 7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED

30 OCT 97 12:29 P.M.

ROBERT W. SMITH REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column D and row 7.

I, Marvin E. Myers, in a field survey on August, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 Wm. Burt, D.S. LCRC Liber 1, pg. 220 J. Wilcox, P.S. #14102
Mon. - Post November 1981
WIT: 10" Beech N33°W 15 lks. Mon. - Set rerod midway & on line
10" Beech S22°E 7 lks. WIT: 3" Maple N87°W 9.16'
2" Maple N69°E 20.84'
10" Oak N13°W 9.67'
6" Maple S16°W 31.49'

SURVEY & REMONUMENTATION

APR 07 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


SECTION

Found 1/2" bar & cap #14102 Accepted as a reestablishment of the original government corner replaced with 1/2" bar & cap with standard Roscommon County monument
Found nail & blaze 4" Maple N81°W 9.18'
Found nail & blaze 3" Maple N73°E 20.8'
Found nail & blaze 12" Red Oak N08°W 9.69'
Found nail & blaze 6" Maple S18°W 31.52'
Centerline trail 15' South

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE OCT 2, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Roscommon County monument
WIT: Nail & blaze in 4" Maple N81°W 9.18'
Nail & blaze in 3" Maple N73°E 20.8'
Nail & blaze in 12" Red Oak N08°W 9.69'
Nail & blaze in 6" Maple S18°W 31.52'
Centerline trail 15' South



Signed by [Signature]

Date October 24, 1997

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

LIBER 3 PAGE 426