

**SURVEY &
REMONUMENTATION**

9560

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon
(County)

Located In:

Corner Code #

23 DEC 96 9:49 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

- | | | | | | |
|------------------------------------|---|------------|---|-----------|--------------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>1W</u> | <u>E - 1</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous | S | | T | | R |
| Property in Section | S | | T | | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on NOV 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-John Brink May 1839
Mon.-Post
WIT: 6" Pitch Pine N55°E 42 lks.

GLO William Burt June 1852
WIT: 8" Y.Pine S80½°E 13 lks.
Old Bearing 6" Aspen
S50°W 39 lks.

US GLO Guy Veal 1937
Mon.-Intersection of Road is accepted as a perpetuation of the original corner position.
Set a block of concrete 8" long 6" in Dia. 18" in the ground to mark corner
WIT: Wit. Mon. N45°E 71 lks.
6" dia. x 24" with 3½" dia. Brass Tablet from which the following witnesses were taken:
5" J.Pine N23 ¾°E 20 lks.
6" J.Pine N18½°W 16 lks.

G.D. Henning July 1, 1975
L.171, pg.519 (Crawford County)
Mon.-None given
WIT: None given

F.J. Arleth July 25, 1975
Mon.-½" bar
WIT: 16" B.Oak N31°W 110.3'
14" B.Oak N48°E 73.7'

G.D. Henning July 25, 1975
L.148, pg.161 (Crawford County)
Mon.-None given
WIT: None given

Henning 1942

PLAT OF SILVER WOODS
L.3, pg. 30 (Crawford County Records)
Sept. 1971

L.2, pg.436
Mon.-½" Bar in place GLO Mon.
WIT: Mon. N45°E 46.9' wit. mon.
16" B.Oak N31°W 110.3'
14" B.Oak N48°E 73.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" bar in water valve box
Found 16" B. Oak N31°W 110.3'
Found 14" B.Oak N48°E 73.7'
Found ½" Bar N39°W 48.47'

Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced ½" bar with Mon. Box & standard Roscommon County Monument
WIT: 6" W.Pine N60°E 55.14'
6" Spruce N39°W 67.43'
Stop Sign Post North post S77°W 69.81'
6" J.Pine S31°E 58.80'
½" Bar N39°W 48.47'

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE NOV 8th 1996

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date NOV 25, 1996