

9167


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T24N	R 1W	F-1
T	R	
T	R	
T	R	



FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey May 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1839
SET POST
PITCH PINE 6" N17 1/2°E 1.01 CHNS
PITCH PINE 6" N7 1/2°W 99 LKS

T.N. CANADA 1937
POINT OF 1/4 COR DETERMINED FROM REAMAINS
OF THE ORIGINAL BEARING TREES
SET CONC MON 6" DIA X 24" BRASS CAP & STEM
(REMAINS OF ORIGINAL BEARING TREES)
FALLEN J. PINE 9" N186E 101 LKS
CHARRED J. PINE STUMP N7 1/2°W 99 LKS
(NEW BEARING TREES)
POPLAR 6" N5 1/4°E 81 LKS
BLACK OAK 5" N61 1/4°E 109 LKS

G.D. HENNING, RLS 1942
SURVEY OF TOWNSHIP CEMETARY
FD GLO MONUMENT IN ROAD

G.D. HENNING, RLS 1973, SEC SURVEY
RE-ESTABLISHED N 1/4 POST ACCORDING
TO 1942 CEMETARY SURVEY AND
MEASUREMENT ON NORTH LINE
SET 1/2 X 36" IRON BAR
8" R. OAK S41°W 54.9'
8" R. OAK S65°E 55.8'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 36" CAPPED IRON #2240 (HENNING)
8" R. OAK (NOW 10") S41°W MEASURED 54.65'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD CRAWFORD COUNTY MONUMENT STAMPED 17614
WT: NAIL & TAG IN 10" R OAK S56°W 24.10'
NAIL & TAG IN 17" R. OAK S02°W 29.37'
NAIL & TAG IN 14" R. OAK N45°E 108.18'
NAIL & TAG IN 11" R. OAK N026E 70.0'
CARSONITE POST NORTH 30.93'

SURVEY &
RECORDATION

MAR 1 2000

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Sept 10, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date Sept. 17, 1999
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

