

OCT 05 1998

2923

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

Roscommon  
(County)

Located in:

Corner Code #

20 APR 98 2:18 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

To be filed in Liber 3 of Land  
Corners

Register of Deeds Stamp & File Number

- 1. Public Land Survey      T 24N R 1W      F-13  
                                   T 23N R 1W      F-1  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on March 2, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838 Lewis Clason, DS  
Mon. - Post  
Wit: 6" White Birch S52°W 5 links  
5" Tamarack N41°E 42 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2"x36" pipe.  
Found blazed 8" Jack Pine (dead) N05°W 16.77'  
Accepted as the best available evidence of the position of the Original Corner.  
Replaced 2" pipe with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument.  
Wit: Set Carsonite Post 1' South.  
Set nail & tag in Southwest face 6" Jack Pine S23°E 5.72'  
Set nail & tag in South face 8" Jack Pine N87°E 30.64'  
Set nail & tag in East face 14" Red Pine North 33.63'  
Set nail & tag in North face 10" Jack Pine S80°W 19.99'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MARCH 27<sup>th</sup> 1998

Marvin E. Myers  
Marvin E. Myers, P.S.  
County Surveyor



Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date April 10, 1998

LIBER 3 PAGE 496