

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF ROSCOMMON

9248

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Dec 28 10 47 AM '93

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24</u> R <u>1 W</u>	<u>G - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Robert J. Arleth*  
REGISTERED

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-14-93**

Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

William Burt 1852  
Tamarack 5" S52°W 38 Lks.  
Tamarack 8" N52°E 25 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Henning 1947 1/2" x 36" bar found witness 10" Cedar S19°W 33.7 7" Cedar S65°E 17.0	North Central Survey Company, 1975 Found 1/2" bar set by Henning, Distance changed slightly witness 12" Cedar S19°W 33.55 10" Cedar S65°E 17.10
Note: above corner was set by DeLaMater date unknown.	
Wilcox in 1981 Found 1/2" bar and rewitness:	S20°W 5" Cedar 7.80 S19°W 12" Cedar BT 32.8 S40°E 5" Tamarack 17.85 S65°E 8" Cedar BT 17.21 N50°E 8" Tamarack 12.10

Arleth Land Survey Company 1987 used above corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Std Mon stamped G-7  
Nail & Tag 5" Blazed Cedar stump S20°W 7.88  
Nail & tag 12" Cedar (BT) S19°W 33.00  
Nail & tag 5" Tamarack S40°E 17.90  
Nail & tag 8" Cedar (BT) S65°E 17.21  
Nail & tag 8" Tamarack N50°E 12.10  
Carsonite post next to corner



Signed by *Frank J. Arleth*

Date 22 DEC 93

Surveyor's Michigan License No. 21266

Date December 14, 1993

Peer Group Approved