

925018 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON
REGISTER

LAND CORNER RECORDATION CERTIFICATE

DEC 28 10 47 AM '93

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Roscommon

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 24 R 1 W G - 9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Robert J. Arleth
REGISTER

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

William Burt set post 1852
Spruce pine 6" S55°W 15 Lks.
Spruce pine 5" N69°E 9 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Wilcox, 1981 set 1/2" bar & cap by double proportion
Arleth land survey company, 1993 found 1/2" bar and all of Wilcox witness.
12" R. pine N71°E 12.51
10" R. pine S68°E 30.67
11" R. pine S25°E 10.22
14" R. pine S86°W 25.97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Std. Mon Stamped G-9
Spike in 12" R. pine N71°E 12.51
Spike in 10" R. pine S68°E 30.67
Spike in 11" R. pine S25°E 10.22
Spike in 14" R. pine S86°W 25.97
Set Carsonite post 2.0 West of corner

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by *Frank J. Arleth*

Date 22 DEC 93

Surveyor's Michigan License No. 21266

Date December 14, 1993 Peer Group Approved