

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T24N R 1W H-1  
T R  
T R  
T R

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED  
6 OCT 1999 11:35:35 AM  
ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey May 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1839  
SET POST  
YELLOW PINE 9° N32 1/2° E 1.01 CHNS  
YELLOW PINE 8° N12° W 35 LKS

T.N. CANADA 1937  
FD REMAINS OF ORIGINAL B TREES  
SET CONC MON 6" DIA X 24"/BRASS CAP & STEM  
NORWAY PINE ST. 10' N12 1/2° W 35 LKS  
NORWAY PINE ST. 10' N34 1/4° E 101 LKS  
(LOCAL BEARING TREES)  
NORWAY PINE 3° N34° E 80 LKS  
J. PINE 6" N48 3/4° W 70 LKS  
(NEW BEARING TREES)  
NORWAY PINE 10° N30 1/2° E 140 LKS  
NORWAY PINE 9° NORTH 149 LKS

LCRC 1970'S L2, P434  
CONC MON  
N34° E 52.8 3' NORWAY  
N49° W 46.2 6' J. PINE  
N30° E 92.4' 10' NORWAY  
NORTH 98.3 9' NORWAY

FRANK ARLETH, RLS 1988  
NO MONUMENT MATERIAL CALLED OUT  
8' J. PINE STP N48° W 46.2'  
12' N. PINE N28° E 92.4'  
10' N. PINE NORTH 98.3'

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND GLO MONUMENT /BRASS CAP  
NORWAY PINE 3° N34° E 52.8'  
J. PINE 6" N49° W 46.2'  
NORWAY PINE 10° N30° E 92.4'  
NORWAY PINE 9° NORTH 93.3'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT US-GLO MONUMENT IN PLACE  
WIT: NAIL & TAG IN 4' W. PINE N43° W (NEW) 25.23'  
NAIL & TAG IN 5' MAPLE S37° E (NEW) 39.08'  
NAIL & TAG IN 9' MAPLE S31° W (NEW) 33.20'  
NAIL & TAG IN 12' N. PINE N34° E 52.95' (OLD)  
CARSONITE POST SOUTH 26.72'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Sept 10, 1999  
*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date Sept. 14, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

SURVEY &  
RECORDS



LIBER 3

PAGE 614

MAR 11 2000

SECTION