

APR 07 1998

7872

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in Roscommon (County) Located In: Corner Code #

1. Public Land Survey	T	24N	R	1W	H - 7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

30 OCT 97 12:30 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on July, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3			2				
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 Wm. Burt, D.S. Mon. - Post WIT: 8" Tamarack N20°E 15 lks. 10" Maple S31°W 16 lks. 7" Cedar N87°46'W 153 lks. Enter swamp N87°46'W 300 lks.	1971 L.L. Cavanagh, PS #17614 Mon. - Fd. 2½"x4" Cedar stake WIT: 3" Cedar S27°W 28.4' 14" Tw. Maple N43°W 32.4'	Liber 2, pg.446 LCRC Mon. - 2½" x 4" Cedar stake WIT: 3" Cedar S27°W 28.4' 14" Tw. Maple N43°W 32.4'
Oct. 4, 1947 G. Henning Mon. - 2½" sq. Cedar Post WIT: BT 3" Cedar S27°W 28.4' BT 14" Tw. Maple N43°W 32.4'	Liber 306, pg.220 April 7, 1975 L.L. Cavanagh, PS #17614 Mon. - 2½" X 4" Cedar stake WIT: ½"x18" bar & cap N88°29'W 212.9' ½"x18" bar & cap S88°29'E 305.1'	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" bar & cap #17614  
Found blaze in 20" twin maple 32.79' N30°W  
Found blaze in 4" Cedar 23.0± S47°W (cedar blown over took measurement at base of tree)  
Found ½" bar & cap #17614 & #215.70 N85°W 212'±  
Found ½" bar & cap #17614 & #215.70 S85°E 305'±  
Accepted position as the best available evidence of the position of the original corner

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Aug 10, 1997 MRM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Roscommon County monument  
WIT: Nail & tag in 20" Tw. Maple N30°W 32.82'  
Nail & tag in 8" Tw. Maple N35°E 19.64'  
Nail & tag in 10" Maple S35°E 20.89'  
Nail & tag in 4" Spruce S29°W 9.69'



Signed by Marvin E. Myers Date October 24, 1997  
Surveyor's Michigan License No. 31600

LIBER 3 PAGE 429