

**SURVEY &
REMONUMENTATION**

2025

OCT 05 1998

**SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>1W</u>	<u>H-13</u>
	T <u>23N</u> R <u>1W</u>	<u>H-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

20 APR 98 2:18 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

To be filed in Liber 3 of Land
Corners

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on March 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>H-13 G.L.O - 1838 Lewis Clason, DS Mon. - Post 8° W. Birch N88°E 20lks. 6° W. Birch N35°W 16 lks. 1900's Marcus Schaaf Michigan Department of Conservation Mon: Found or established and replaced</p>	<p>L. 1, Pg. 101 (Herbert L. Fluharty P.S. # 18223, 9-11-1974 Mon. - Found 2" wood stake in ground next to rotted 4" Sq. stake; Set 5/8" Iron and Cap next to 2" wood stake 8" Balsam N77°W 23.23' 10° W. Birch N03°E 16.23' 11° W. Birch S70°E 6.02'</p>
---	---

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MARCH 27th 1998**

Marvin E. Myers

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" IP set in concrete (typical Schaaf monument) 185± South of centerline of Marl Lake Road.
Found 1/2" bar & cap #11368 J. R. Radcliffe, P.S. N78°E 0.66'
Found blazed 8" Balsam with spike N68°W 22.95'
Found blazed 14" Balsam set nail & tag in Southwest face N81°E 51.67'
Did not accept the 1/2" bar & Cap #11368, which apparently was set at the location of the wood stake set along side the schaaf monument as an accessory. Accepted the 1 1/4" IP set by Schaaf as a perpetuation of the Original Government Corner. Replaced 1 1/4" IP with Standard Roscommon County Monument.

**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument.
Set nail & tag above over grown nail in 8" Balsam N68°W 22.95'
Set nail & tag in Southwest face 14" Balsam N81°E 51.67'
Set nail & tag in East face 4" Jack Pine S03°E 8.05'
Set nail & tag in East face 4" Maple N25°W 12.33'
Set Carsonite Post 1' South.



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date April 10, 1998

LIBER 3 PAGE 498