

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>16</u> T <u>24N</u> R <u>2W</u> S <u>16</u> T <u>24N</u> R <u>2W</u>	<u>5</u> <u>6</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on July, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5 - None

6 - None



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

5 - CN 1/16 Cor Sec. 16 -
 - Set 2" A.C. on 5/8" x 34"
 Rebar per Standard BLM Procedure

6 - NE 1/16 Cor. Sec. 16
 Set 2" A.C. on 5/8" x 34"
 Rebar per Standard BLM Procedure

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - Mon per part "B" w/Carsonite Guard Post
 N25°E 11.25' to N&T in W. Side 7" J. Pine
 S85°E 21.79' to N&T in N. Side 4" B. Oak
 S19°E 30.95' to N&T in NE Side 4" B. Oak
 S20°W 18.97' to N&T in NW Side 9" J. Pine

6 - Mon per Part "B" w/Carsonite Guard Post
 N72°W 16.75' to N&T in S. Side 10" B. Oak
 N24°E 27.76' to N&T in W. Side 9" B. Oak
 S86°E 20.29' to N&T in N. Side 3" B. Oak
 S22°W 14.59' to N&T in W. Side 8" J. Pine

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 1/22/1997