

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>16</u> T <u>24N</u> R <u>2W</u>	<u>13</u>
	S <u>16</u> T <u>24N</u> R <u>2W</u>	<u>14</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on July, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

13 - None

14 - None



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

13 - SE 1/16 Cor. Sec. 16
 Set 2" A.C. on 5/8" x 34"
 Rebar per Standard BLM Procedure

14 - S 1/16 Cor. Sec. 15 & 16
 Set 2" A.C. on 5/8" x 34"
 Rebar per Standard BLM Procedure
 Mon 10' ± W of CL. N-S Logging Rd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 - Mon per part "B" w/Carsonite Guard Post
 N5°W 64.36' to N&T in W. Side 2" B. Oak
 N48°E 38.56' to N&T in SE Side 5" J. Pine
 N78°E 42.72' to N&T in S. Side 5" J. Pine
 S75°W 101.75' to N&T in N. Side 3" B. Oak

14 - Mon. per part "B"
 S68°W 6.95' to N&T in N. Side 7" W. Pine
 N7°E 27.23' to N&T in W. Side 3" Maple
 N25°W 17.63' to N&T in SW Side 5" W. Pine
 S55°E 53.53' to N&T in NE Side 2" Maple
 S1' Carsonite Post

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 1/22/97