

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| For Corners In: Roscommon (County) | Located In | Corner Code # |
|--|--------------------------|---------------|
| 1. Public Land Survey | T <u>24N</u> R <u>2W</u> | <u>B-9</u> |
| | T <u>24N</u> R <u>2W</u> | <u>C-10</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on September 12, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | ● | | | | | | | | | | | | |
| 10 | 30 | ● | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

B-9. G.L.O. William Burt in 1852 set quarter section post
 Wit: Y. Pine 6" S63°W 13 links
 Y. Pine 8" N65°E 9 links

C-10 G.L.O. William Burt in 1852 set quarter section Post
 Wit: Tamarack 7" S38°E 17 links
 Tamarack 8" N46°W 27 links

Jan. 25, 1966 MDOT set a regulation conservation department cap and pipe by single proportion method, between accepted corners. No evidence of original corner or bearing trees.

Wit: S28°E 18.90' 7" Oak
 S70°W 40.05' 7" Oak
 N31°E 63.86' 8" Oak
 N58°W 49.62' P. Pole

Jan. 25, 1966 MDOT found 4" by 4" Cedar post as set by G.F. DeLaMater from remains of both government bearing trees. 1966 MDOT set Conservation Department regulation cap and pipe at post and new 4" by 4" Cedar post.

Wit: N26°W 13.44' 11" Cedar (G.F.D. NBT)
 S78°W 8.79' 10" Cedar (G.F.D. NBT)
 S51°E 8.88' 10" Cedar (G.F.D. NBT)
 S45°E 12.81' 10" Cedar (NBT)

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-9 Found Conservation monument as set by MDOT.
 (corner was set online prorated to U.S. runout)

C-10 Found a 4" X 4" cedar post laying down. Set a standard DNR monument from G.F. DeLaMater and MDOT witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 Found Conservation cap on 1" pipe
 Wit: 3" Maple S03°E 33.44'
 3" Maple S89°E 27.93'
 P. Pole N47°W 49.55'
 10" Maple N35°E 72.82'
 Carsonite Post North 1'±
 Centerline of 2 track road North 20'

C-10 Set 1" X 32" Pipe with DNR cap
 Wit: 14" Cedar S35°E 12.90'
 Cedar stump NBT S56°E 8.80'
 5" Balsam S55°E 10.73'
 13" Cedar N80°E 18.34'
 12" Cedar N20°W 7.66'
 12" Cedar S76°W 9.02'
 Carsonite Post North 1'±

Signed by: Carl T. Kiiskila

Date: 9-20-06

Surveyor's Michigan License No.: 33981

