

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

For corners in

Roscommon
 (County)

Located In:

Corner Code #

6 MAY 99 2:09 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>24N</u> R <u>2W</u> | <u>A-2</u> |
| | T <u>24N</u> R <u>3W</u> | <u>M-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

To be filed in Liber 3 of Land Corners
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838	George D. Henning, R.L.S.
John Brink D.S.	Misc. Surveys Section 6, T24N, R2W dated December 1941
Mon. - Post	Mon: 1 1/4" pipe
Wit: 8" Tamarack S67°E 20 links	Wit: 7" Elm S86°E 26.3' 12" Elm S8 1/2°W 11.9'
8" Tamarack S34°W 38 links	9" Elm N54°W 77.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1 1/4" x 4' long pipe of record in the intersection of old fence lines North - South and East.
 Found 20" Elm Stump (recorded previously as 9") N54°W 77.8'
 Accepted 1 1/4" pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County corner.
 Wit: Set Carsonite Post S05°W 3.47'
 Set nail & tag in N. face 16" Tamarack N88°E 21.20'
 Set nail & tag in 12" Maple S70°W 104.25'
 Set nail & tag in NW face 12" Maple S21°W 91.98'
 Set nail & tag in 4" Balsam N07°W 23.78'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE April 19, 1999 *MEM*

Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor



Signed by _____

Date April 24, 1999

Surveyor's Michigan License No. 31600