

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

COMMISSION

9587

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

23 DEC 96 1:00 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>24</u> R <u>2</u> W	<u>A - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Frank J. Arleth, in a field survey on November, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

John Brink 1836	State Hwy Dept. 3/4" bolt
Y. Pine 18" S64°E 61 lks	S52°W 87.44 pipe ( gas #12)
Y. Pine 18" N54°E 32 lks	N24°E 53.25 14" Oak
	S48°E 47.85 Ref. cap in large Rock
	corner in centerline of road N&S
	5' South of centerline E & W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4 " bolt  
N24°E 53.25 14" Oak  
S48°E 47.85 ref. cap in large rock

**ROSCOMMON COUNTY**  
**PEER GROUP APPROVAL**  
DATE NOV 8<sup>th</sup> 1996

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Standard Mon. Stamped 21266 M-9  
Spike in 8" J. pine S30°W 104.14  
Spike in 16" B. Oak S42°E 80.75  
N 24°E 47.85 ref. cap in large rock  
Center line gas pipe marker ( face of ) N60°W 77.85  
Carsonite Post S48°E 48.75 by stone witness.



Signed by *Frank J. Arleth* Date NOV 8 1996

Surveyor's Michigan License No. 21266 P. S.  
Date: NOV 96 peer group approved.