

**SURVEY & REMONUMENTATION**

ROSCOMMON COUNTY REMONUMENTATION

8369

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

Roscommon (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>24</u> R <u>2 W</u>	B - 5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

15 NOV 94 9:12 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Frank J. Arleth, in a field survey on November 19 94

I, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Brink 1837 - Burt 1852 Set Post  
S. Pine 10" N 25°W 43 Lks  
Y. pine 8" N50°E 64 Lks  
Y. pine 6" 1.10 West  
½" x 30" bar set by Delmater in 1929.  
Y. pine 24" S18°E 36.4 ( now stump)  
10" B. Oak S32°W 28.8 ( destroyed)

R. C. R. C. witness:  
18" R. Oak N65°E 44.98 ( P.K. OK)  
18" R. oak S10°W 31.98 ( P.K. ok)  
18" R. Oak S35°W 28.8 ( gone )  
Corner found and used by Henning in Section 18 section subdivision 1952. Corner used by Ostling, Cavanagh & Arleth in subsequent surveys of record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Arleth found ½" bar in October 1994, above R. C. R. C. witness still in place.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Roscommon County Standard monument. B-5  
P. K. Nail in 24" R. Oak N61°E 44.98  
N & T 15" R. Oak N25°E 39.88  
N & T 15" R. oak N35°W 63.46  
N & T 16" W. oak N78°W 49.0  
P.K. nail in 18" R. oak S10°W 31.98 (dead)  
½" bar cap No. 21266 South 33.0'.  
Carsonite survey post 2.0 North

Corner is in bank of trail road on North side of road.



Signed by Frank J. Arleth  
Surveyor's Michigan License No. 21266 P. S.

Date 11/10/94

DATE 10/20/94

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

*MEM* LIBER 3 PAGE 149