

SURVEY & REMONUMENTATION

8364

APR 24 1995

**ROSCOMMON COUNTY REMONUMENTATION
COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

15 NOV 94 9:06 A.M.

ROBERT W. SKITH
REGISTER OF DEEDS

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24</u> R <u>2</u> W	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frank J. Arleth, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Cedar Post Brink 1837 - Burt 1852
Tamarack 10" N49°W 13 Lks
Spruce 8" S57°W 25 Lks

Corner set by Delamter 1924, 1/2" x 30" bar
2" Elm N78°W 35.3
24" W. pine S28°E 17.7

1944 Henning & Ostline found corner to be replaced by D.N. R. Monument which is a 4" pipe filled with concrete with brass cap.

Henning used corner in 1952 for Section subdivision of Section 7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Arleth found 4" pipe with brass cap, 1994. Above witness destroyed. Stream ties 106' more or less East and 130' more or less South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Used 4" pipe with brass cap for corner. C-5
N & T 24" N. pine N7°W 59.00
N & T 10" spruce N 57°W 43.94
N & T 10" Tamarack S12°W 38.40
N & T 8" spruce S72°W 23.52
N & T 6" spruce S50°E 28.52
Carsonite Survey marker at corner.



Signed by Frank J. Arleth Date 11/10/94
Surveyor's Michigan License No. 21266 P.S.

DATE 10/20/94 Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993

MEM LIBER 3 PAGE 144