

4619

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

11 JUL 97 4:10 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R2W	C-1
T24N	R2W	C-13
T	R	
T	R	

I, Larry L. Cavanagh, in a field survey June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

SET POST WILLIAM BURT 1852  
WIT: W PINE 20 N55°W 54'  
TAM 5 N46°E 54'

NORMAN C. CALDWELL RLS 12018, 1966  
FD 4" X 4" POST 1/2" BAR, SET BY  
DELAMATER FROM ORIGINAL GOV B.T.S.  
SET REGULATION CONSERVATION DEPT. CAP  
AT CORNER & NEW 8" X8" CEDAR POST  
CORNER IS IN BACKWATERS OF ROBINSON  
FLOOD AREA & 212 FEET SOUTH OF E-W ROAD

(IN OLD 14"X17" SURVEY BOOK AT REG OF  
DEED)

G.E. DELAMATER 1932  
FD GOV'T BEARING TREES AND POST  
SET 1/2" X 30" BAR  
W PINE 12" N1°W 101.8'  
CEDAR 2" N40°E 16.7'  
B. ASH 5" S15°W 23.6'

LCRC LIBER 2, PAGE 498  
DNR CAP & PIPE  
8"X8" CEDAR POST  
CORNER IN FLOOD AREA 212' S. OF E-W ROAD

SCHAAF RECORD (FOUND & REPLACED)

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONSERVATION DEPT MONUMENT  
NO WITNESSES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CONSERVATION DEPT MONUMENT LEFT IN PLACE  
WIT: NAIL & TAG IN 12" MAPLE S67°W 132.70'  
NAIL & TAG IN POWER POLE N48°W 270.23'  
NAIL & TAG IN POWER POLE N34°E 224.69'  
CARSONITE POST SOUTH 2'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE July 8, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983