

**SURVEY & REMONUMENTATION**

8361

ROSCOMMON COUNTY REMONUMENTATION

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in  
ROSCOMMON  
(County)

Located In: \_\_\_\_\_ Corner Code ≠#

15 NOV 94 9:06 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>24</u> R <u>2 W</u> | <u>D-3</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

TO BE FILED IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frank J. Arleth, in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

BURT 1852 SET A POST  
S. Pine 8" N41°E, 118 Lks.  
S. Pine 8" S65°W, 51 Lks.

Found by Henning & Ostling 1943  
Used as the NE. Corner of The Assessor's Plat Of Wyckoff Addition To Roscommon, Recorded in L, 3 of Plats, P, 11, Roscommon Co. Records. Conc. Mon. in Cor. and Mons. 33' So. and 33' West.

Set Mid-Way and on line between Sections Corners by George F. DeLamater with Bricks for corner.  
Mound of Earth N42°W, 50.0'  
72.0' West of West Rail of Railroad.

Corner used in Subsequent Surveys by Henning, Ostling, Cavanagh and Arleth.  
Roscommon County Road Commission Witnesses N&T in Power Pole S80 W, 68.32'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Arleth 1994 Found T-Iron over Concrete Monument 20' below Blacktop in Centerline of Ballinger Street  
Found N&T in Power Pole S80°W, 68.32'  
Found N&T in Power Pole S10°W, 23.71' (Moved)  
Center of Fire Hyd. N65°W, 66.80'

N&T in Power Pole S10°W, 23.71'  
Center of Fire Hyd. N65°W, 66.80'



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET ROSCOMMON COUNTY STANDARD MONUMENT D-3.  
Roscommon County Road Commission Fence Corner N72°30'E, 88.73'  
SW. Corner of Roscommon County Road Commission Garage Building N13°E, 108.07'  
N&T in Power Pole S73°W, 69.10'  
N&T in Fence Post S49°W, 47.30'  
Center of Top Nut of Fire Hyd. N58°W, 66.83'  
N&T in Power Pole S39°E, 20.51'  
CARSONITE SURVEY POST SET S38°E, 21.0'

Signed by Frank J. Arleth Date 11/10/94  
Surveyor's Michigan License No. 21266

DATE: 10/20/94 Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

**LIBER 3 PAGE 141**