

SURVEY & REMONUMENTATION

8360

APR 24 1995

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

For corners in

Roscommon
 (County)

Located In:

Corner Code #

15 NOV 94 9:05 A.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

- | | | | | | |
|------------------------------------|---|----|---|------|-------|
| 1. Public Land Survey | T | 24 | R | 2 w. | D - 5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			9										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frank J. Arleth, in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

William Burt set post 1852
 S. pine 8" S83°W 345 Lks
 S. Pine 8" S86°30E 1000 Lks
 DeLamater 1929 set 4" pipe in corner
 No witness

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Arleth October 94 found concrete pieces at corner location 4" pipe was destroyed.
 Set corner midway & on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County standard monument D-5
 trail rods N & S and E & W
 1 1/4 " pipe N 40°E 17.20
 N & T 6" J. pine N61°30E 30.81
 N 7 T 10" J. pine S62°30"E 68.10
 N & T 12" J. pine S20°E 34.84
 N & T 8" J. pine S54°30'W 74.88



Signed by Frank J. Arleth

Date 11/10/94

Surveyor's Michigan License No. 21266 P. S.

DATE 10/20/94

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 3 PAGE 140