

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich P.A. 1970**

For corners in  
 Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R2W	D-1
T24N	R2W	D-13
T	R	
T	R	

STATE OF MICHIGAN  
 ROSCOMMON COUNTY  
 RECORDED

11 JUL 97 4:10 P.M.

ROBERT W. SMITH  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

SET POST BY WILLIAM BURT, 1852  
 WIT: W. BIRCH 5 N5°E 3  
 CEDAR 5 N85°W 11

KENNETH J. OSTLING RLS 10068, 1983  
 SET DNR MONUMENT  
 WIT: 10" HEMLOCK, N34°W 50.7  
 16" CEDAR N69°W 26.5'  
 6" CEDAR S37°W 21.5'  
 DNR MON S0°04'44"W 1568.91'  
 SET 4" CEDAR POST BY CORNER

SCHAAF RECORD INDICATES  
 FOUND AND REPLACED

(IN OLD 14"x17" SURVEY BOOK, REG  
 OF DEEDS)  
 G.F. DALAMATER 1932  
 SET 1/2" X 30" BAR @ COR PLACED  
 MID-WAY ON LINE  
 HEM 7" N34°W 50.7  
 CEDAR 6" N69°W 25.5'

CARL KIISKILA RLS, 1997  
 LIBER 744, PAGE 14 (RECORDED SURVEY)  
 FD DNR MON. SET BY K.J. OSTLING IN 1983  
 10" HEMLOCK N34°W 50.7  
 16" CEDAR N69°W 26.5'  
 6" CEDAR S37°W 21.5'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DNR MONUMENT  
 10" HEMLOCK N34°W 50.7'  
 16" CEDAR N69°W 26.5'  
 6" CEDAR S37°W 21.5'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR MONUMENT LEFT IN PLACE  
 NAIL & TAG IN 10" HEMLOCK N34°W 50.7'  
 NAIL & TAG IN 6" CEDAR S37°W 21.5'  
 \*NAIL & TAG IN 10" MAPLE S86°W 10.41'  
 \*NAIL & TAG IN 5" BALASM S86°E 53.09'  
 CARSONITE POST NORTH 2.54'

\* NEW WITNESSES

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY**  
**PEER GROUP APPROVAL**  
 DATE July 8, 1997

*Marvin E. Myers*  
**Marvin E. Myers, P.S.**  
 County Surveyor

Signed by *Larry L. Cavanagh*  
 Surveyor's Michigan License NO. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

