

9549

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

23 DEC 96 9:46 A.M.

For corners in
Roscommon _____
(County)

Located In:

Corner Code #

ROBERT W. SMITH
REGISTER OF DEEDS

- 1. Public Land Survey T 24N, R 2W E-1 _____
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

SURVEY &
REMONUMENTATION

MAY 28 1997

Register of Deeds Stamp & File Number
COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Marvin E. Myers, P.S., in a field survey on Nov 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-June 1852 W. Burt L.163, P.550 F.J.Arlenth 1977 L.3, P.35 M.E.Myers 1991
Mon-Post Mon-3/4" Bar Mon- 3/4" Bar
- Wit-8" P.Pine N53°W 68 Lks Wit-1' South of edge of pav't Wit-Face of utility pole S40°W 18.08
7" P. Pine N52½°E 27 Lks 12" Pine N42½°E 91.30 NE Corner "Dan's Flies" Sign Post S45°E 27.03
12" Spruce pine N30°E 78 Lks 15" R. Pine N10½°W 104.10 15" R. Pine N10½°W 104.10
12" Spruce Pine N42°W 79 Lks E. Edge Stop Sign post N02°W 51.80
- G.D. Henning & R.T. Ostling 1949 L.186, P. 36 N.F. Parker 1980
Mon-5/8" Iron bar Mon-none given Wit-none given
- R.T. Ostling 1961, 1963, 1973
Mon-3/4" Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Bar on South side of road 1'± South of edge of pavement; found 1" bar along side 3/4" Bar
Found Utility Pole S40°W 18.08
Found 15" R. Pine N10½°W 104.10

Accepted as the best available evidence of the position of the original corner.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE NOV 22 1996

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced with Standard Roscommon County Monument
- Wit: Nail & tag in "Deerheart Valley Road" Sign Post N50°E 66.98
Nail & tag in Telephone pole N48°W 72.04
Nail & tag in Telephone Pole S44°W 18.38
4" B. Oak S58°E 85.48



Signed by *Marvin E. Myers* Date Dec 24 1996
Surveyor's Michigan License No. 31600

LIBER 3 PAGE 340