

8753

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Roscommon (County)

Located In:

Corner Code #

- 1. Public Land Survey T 24 R 2 W E-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 DEC 95 9:10 A.M.

Register of Deeds Stamp & File Number
ROBERT W. SMITH
REGISTER OF DEEDS

- 4. Lot No. Recorded Plat
5. Private Claims

COMMISSION

Grid table with columns A-M and rows 2-13. Cell 4,9 contains a circle with the number 0.

I, Frank J. Arleth, in a field survey on January, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- William Burt 1852 S. Pine 8" N60°W 401ks S. Pine 6" S62°E 211ks
G. F. DeLamater 1929 Fd. Old post. Set Cedar Post 5' J. Pine S60°E 22.0' 6" J. Pine N10°W 20.0'
Henning 1952 Fd. Cedar Post, set 1/2" x 48" bar. Wit. Fd old BT 12" J. Pine N11°W 20.0' New: 8" J. Pine N26°E 28.0' Henning 1961 fd & used 1/2" bar- witness O. K.
Williams & Works 1971 Fd 1/2" bar Sp. 12" pine N21°E 8.02' Sp. 8" Oak S85°E 6.20' Sp. 12" Oak South 51.5' Arleth 1995 Fd. 1/2" bar Fd 12" J. Pine Stump N11°W 20.0' Fd sp 12" Oak South 51.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Arleth, January 1995 Fd. 1/2" x 48" bar Fd 12" J. Pine stump N11°W 20.0 - Henning Fd sp in 12" Oak South 51.5' W & W Other witness gone Swamp North 67.0'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-8-1995

Signature

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Roscommon County Standard Monument Stamped E-4 (21266) Sp. 16" B. Oak S2°W 51.50' (old) N & T 20" N. Pine S25°W 64.06' N & T 14" N. Pine N48°W 70.85' N & T 8" J. Pine N1°E 47.58' N & T 12" B. Oak S42°E 69.48' Set carsonite post 1.00' South of corner.



Signed by [Signature] Date 12/8/95
Surveyor's Michigan License No. 21266

Date 12/8/95 Peer Group Approval