

3550

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

23 DEC 96 9:47 A.M.

For corners in
Roscommon
(County)

Located In:

Corner Code #

ROBERT W. SMITH
REGISTER OF DEEDS

- 1. Public Land Survey T 24N, R 2W F-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

SURVEY &
REMONUMENTATION

MAY 28 1997
Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Marvin E. Myers, P.S., in a field survey on Nov, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO W. Burt June 1852 Mon-Post Wit- 9" P.Pine N45°W 1.06 Chs 4" P.Pine N63°E 25 Lks.	LCRC L.3, P.34 M.E.Myers Nov. 1991 Mon- Bolt in Pav't Box Wit- Face of U.Pole S55°E 82.00 ½" bar and cap #2240 South 33.00 U.Pole S84°W 103.00
R.T.Ostling 1961 Mon- Pav't Box	Nail in W. Face 5" R. Pine N55°E 62.40 Nail in W. Face 6" J. Pine N11°W 41.56

L.163, P.550 F.J.Arleth 1977
Mon- Pav't Box
L168, P.352 F.J. Arleth 1978
Mon- Pav't Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Bolt in pavement box. Found all accessories recorded in L.3, P. 34.
Accepted as the best available evidence of the position of the original corner.

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE NOV 5th 1996

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard Roscommon County monument in pav't box.
Wit: Utility Pole S84°W 103.00
 ½" bar and Cap #2240 South 33.00
 Nail in West face 5" R. Pine N55°E 62.40
 Nail in W. fance 6" J. Pine N11°W 41.56



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31800

Date Dec 27, 1996

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1971
REVISED JAN., 198

1, REF 3 DATE 341