

4624

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R 2W	H-1
T24N	R 2W	H-13
T	R	
T	R	

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

11 JUL 97 4:11 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey June 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

SET POST BY WILLIAM BURT, 1852  
WIT: W. PINE 18 N48E 20  
MAPLE 12 N47W 18

SCHAAF RECORD INDICATES THAT THIS CORNER  
WAS FOUND AND REPLACED

CARL R. JOHNSON RLS 30083, LCRC  
LIBER 1, PAGE 239, 1986  
FD 1 1/4" PIPE IN CONCRETE SET CEDAR POST  
WIT: 12" RED OAK N28°E 40.2'  
16" RED OAK N61°W 26.6'  
13" RED OAK S43°W 17.1'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1 1/4" PIPE IN CONCRETE, BELIEVED TO BE AS REPLACED BY M. SCHAAF  
12" R. OAK N28°E 40.2'  
16" R. OAK N61°W 28.6'  
13" R. OAK S43°W 17.1'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT #17614 1997  
NAIL & TAG IN 15" R. OAK S43°W 17.58'  
\* NAIL & TAG IN 8" MAPLE CLUMP N54°W 35.73'  
\* NAIL & TAG IN 10 R. OAK N8°E 39.14'  
NAIL & TAG IN 16" R. OAK N28°E 40.45'  
CARSONITE POST SOUTH 2.48'

\* NEW WITNESSES

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE July 8, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License No. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 417