

9273

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Sept 15, 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

SURVEY &

REMONUMENTATION

21 DEC 94 8:38 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Roscommon	Located In:	Corner Code #
(County)		
APR 24 1995		
1. Public Land Survey	T 24N R 2W	I - 1
COMMISSION	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on May 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-1838 J. Brinks Mon-Post WIT: 4" P.Pine N69½°W 13 lks. 6" P.Pine N45°E 34 lks.
- L.2, pg.470 (Same as L.2, pg.469)
- L.320, pg.426 July 1976 F.J. Arleth Mon-Fd. Boat Spike WIT: 9" B.Oak N34 3/4°E 65.20' 3' N. of C. M-18 12" Oak Stump S29½°W 50.80' 7" J.Pine N45½°W 78.60'
- GLO-1852 WIT: 8" B.Oak S40°W 56 lks. 8" S.Pine S45°E 23 lks.
- L.270, pg.648 Dec. 1972 C.E. Ostling Mon-Fd. Boat Spike WIT: 9" B.Oak N34°45'E 65.20' 12" B.Oak S29°30'W 50.80' 7" J.Pine N45°30'W 58.40'
- Sept. 1980 G.D. Henning Mon-Fd. Boat Spike WIT: 9" B.Oak N34 3/4°E 65.20' 7" J.Pine N45½°W 58.40'
- L.2, pg.469 LCRC Mon-Boat Spike WIT: 9" B.Oak N34 3/4°E 65.20' 12" B.Oak S29½°W 59.80' J.Pine N45½°W 58.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found Boat Spike verified position by measurement to corners and accessories of record. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Set Standard Roscommon County monument mark cap "31600".
- Wit-Set nail & tag SW side 11" J. Pine N42°W 78.67.
- Set nail & tag SE side 17" B. Oak N39°E 65.35
- Set nail & tag NW side 9" J. Pine S46°W 70.96
- Found Nail & tag NE side 10" J. Pine (cut off 10' above ground) N49°W 60.62
- Found Nail & tag NE side 8" J. Pine S19°E 48.42

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Dec 15, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983