

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich P.A. 1970**

For corners in  
 Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R 2W	I-1
T24N	R 2W	I-13
T	R	
T	R	

STATE OF MICHIGAN  
 ROSCOMMON COUNTY  
 RECORDED

11 JUL 97 4:11 P.M.

ROBERT W. SMITH  
 REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

SET POST BY WILLIAM BURT 1852  
 WIT: S. PINE 10 N66°W 17  
 S. PINE 8 N39°E 40

SCHAAF RECORD INDICATES NO  
 CORNER FOUND OR ESTABLISHED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" PIPE IN CONCRETE IN NORTH-SOUTH TRAIL ROAD  
 EVEN THOUGH HIS RECORD DOES NOT INDICATE AS SUCH, ITS BELIEVED THAT THIS IS A SCHAAF CORNER BY THE MONUMENT MATERIAL  
 FOUND 3/8" ROD WITH "D" HANDLE 4.6' SOUTH AND 5.2' WEST, NOT BELIEVED TO HAVE BEEN SET BY OR EVER USED BY A SURVEYOR FOR A PROPERTY CORNER. THIS ROD REMOVED.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT #17614 1997  
 WIT: NAIL & TAG IN 22" TWIN B. OAK N60°W 31.18'  
 NAIL & TAG IN 28" W. OAK N14°W 67.68'  
 NAIL & TAG IN 20" B. OAK N42°E 28.28'  
 NAIL & TAG IN 6" W. PINE S32°W 28.76'  
 CARSONITE POST EAST 7.60'

**SURVEY &  
 REMONUMENTATION**

APR 07 1998

SECTION

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY  
 PEER GROUP APPROVAL**

DATE July 8, 1997

*Marvin E. Myers*  
**Marvin E. Myers, P.S.**  
 County Surveyor



Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983