

MAY 28 1997

9555

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Roscommon _____
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey	T	24N	R	2W	L - 1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

23 DEC 96 9:48 A.M.

ROBERT W. SKITH
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Marvin E. Myers, in a field survey on November, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO William Burt June 1852 Mon.-Post WIT: 4" S.Pine N05°E 30 lks. 4" S.Pine N73°W 8 lks.	G.D. Henning 1947 L.3 of Plats, pg.17 DEERHEART WOODS Mon.-Pipe in corner WIT: BT 7" J.Pine N15°W 56.3' BT 5" J.Pine S46°W 99.2'	F.J. Arleth Jan. 13, 1983 L.213, pg.248 (Crawford County) Mon.-Fd. RR Spike
G.D. Henning Oct. 30 1946 Mon.-Set 3/4" Pipe on line at mid point WIT: Mk'd B.T. 7" J.Pine N15°W 56.3' Mk'd B.T. 5" J.Pine S46°W 99.2'	G.D. Henning Aug. 31, 1978 L.174, pg.280 (Crawford County) Mon.- Not given	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box with 1" Iron Bar
Found J.Pine with B.T. Blaze N15°W 56.3'
1/2" bar & cap #2240 North 33.00'
Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1" iron bar with standard Roscommon County Monument
WIT: Nail & tag in P.P. N40°E 37.65'
Nail & tag in P.P. N66°W 87.37'
Nail & tag in P.P. S43°E 42.84'
Nail & tag in 10" J.Pine S19°W 32.34'
Fd. 1/2" bar & cap #2240 North 33.0'



ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE NOV 8, 1996

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers* Date December 13, 1996
Surveyor's Michigan License No. 31600