

9263

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

Dec 28 10 43 AM '93

For corners in COMMISSION
Roscommon
(County)

Located in: Corner Code #

- 1. Public Land Survey T 24 R 2 W L-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

REGISTERED
**ROSCOMMON COUNTY
PEER GROUP APPROVAL**
DATE 12-14-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													0
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frank J. Arleth, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

William Burt set Post 1852
S. Pine 12" N87°E 53 Lks
S. Pine 12" S60°W 28 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Henning Oct 1946 1" pipe in Corner
Wit: 14" B. Oak stump N13°E 68.7 No other visable witness or evidence found
20" B. Oak S80°W 87.5
Concrete mon reset for the S½ corner of Section 1, T24N, R2W.
for AuSable Heights Subdivision (10/17/67) liber 6 page 1

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete plat mon. with cap #21266
Nail & tag 14" W. Pine S81°W 7.03
Nail & tag 14" W. Pine S14°E 55.30
Nail & tag 6" N. Pine N58°W 34.52
Nail & tag 6" N. Pine N64°E 40.95
Carsonite post set 2.0 West



Signed by Frank J. Arleth Date 21 DEC 93

Surveyor's Michigan License No. 21266

Date December 14 1993 Peer Group Approved

LIBER 3 PAGE 89