

9265 18 1894

ROSCOMMON COUNTY REMONUMENTATION

Dec 28 10 48 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24 R 2 W	M-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Robert J. Arleth*  
REGISTER

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-14-93

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Frank J. Arleth, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
William Burt Set Post in North edge of stream 70 Lks wide and runs NW  
Willow 7" S40°W 28 Lks.  
No other tree in area

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1946 Henning found no evidence of corner in true position, said wild corner set by Richardson was 48.5 West & 14.6 North of true position for corner. 1949 Henning set post for corner. 1964, Ostling set 5/8" bar in Henning post. Wit: 8" Elm N20°W 4.2 Found 5/8" bar set by Ostling, also post 3.0 south of corner. Wit: 8" Elm N20°W 4.2 dying. River ties East 16.0', South 20', West 30'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set Roscommon County Std. Mon stamped M-3  
Nail & tag 16" Elm N20°W 25.82  
Nail & tag 12" Elm N55°W 20.25  
Nail & tag 16" Elm N20°W 3.85 - 1964  
Nail & tag 16" Elm stump East 15.2  
Carsonite Post Next to corner



Signed by *Frank J. Arleth*

Date 21 DEC 93

Surveyor's Michigan License No. 21266

Date December 14, 1993

Peer Group Approved