

**SURVEY &  
REMONUMENTATION**  
7875

APR 07 1998

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

30 OCT 97 12:30 P.M.

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
Roscommon  
(County)

Located In:

Corner Code #

ROBERT W. SMITH  
REGISTER OF DEEDS

- |                                      |   |            |   |           |       |
|--------------------------------------|---|------------|---|-----------|-------|
| 1. Public Land Survey                | T | <u>24N</u> | R | <u>1W</u> | A - 7 |
|                                      | T | <u>24N</u> | R | <u>2W</u> | M - 7 |
|                                      | T |            | R |           |       |
|                                      | T |            | R |           |       |
| 2. Property Controlling in Section   | S |            | T |           | R     |
|                                      | S |            | T |           | R     |
| 3. Miscellaneous Property in Section | S |            | T |           | R     |
|                                      | S |            | T |           | R     |

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on July, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Set Post 1839 J. Brink, D.S.  
WIT: 7" Spruce N27½°W 09 lks.  
8" Cedar S55°W 29 lks.

DNR 1963 K. Ostling  
Mon. - Set 1" pipe  
WIT: 18" W.Pine N86°E 23.90'  
9" Cedar S43°E 15.50'  
7" Cedar S27°W 21.30'

L.378, pg.166 June 30, 1997  
L. Beauregard  
WIT: 18" W.Pine N86°E 23.90'  
9" Cedar S43°E 15.50'  
7" Cedar S27°W 21.30'

GLO June 21, 1852 Wm. Burt  
Mon. - Post  
WIT: 10" Tamarack 21 lks.  
12" Cedar S40°E 33 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" Pipe (DNR) monument Brass Cap  
Blaze in 22" W.Pine S87°E 23.94'  
Blaze in 12" Cedar S32°E 15.78'  
Blaze in 8" Cedar S31°W 21.15'

Accepted as a reestablishment of the position of the original government corner

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL**  
DATE Aug 11, 1997

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon.-Left DNR monument in-place  
WIT: Set nail & tag in 22" W.Pine S87°E 24.91'  
Set nail & tag in 12" Cedar S32°E 16.09'  
Set nail & tag in 8" Cedar S31°W 21.28'  
Set nail & tag in 8" Cedar N57°W 9.87'  
Set Carsonite post North 1.13'



Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date October 24, 1997