

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>2W</u>	<u>J-2</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>24N</u> R <u>2W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on June 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3			2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

J - 2 This corner was not established during the original government survey.

9 - This position was not established during the original government survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J - 2 Found and accepted a 1/2" rerod as set by C. E. Ostling, RLS #12026, for the Center of Section 2. The rerod fits his Certificate of Survey recorded in Liber 270, Page 648.

9 - Established the Southwest Corner of the Southeast Quarter of the Northeast Quarter of Section 2 per standard BLM instructions for subdivision of a section.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J - 2 Set 1" x 32" iron pipe with PS cap over the found 1/2" rerod.  
 Witness: Set nail in 3" Jack Pine N 47° E 10.06'  
 Set nail in 8" Red Pine N 62° W 10.61'  
 Set nail in 3" Jack Pine S 66° E 12.73'  
 Set nail in 2" Cherry S 17° W 16.42'

9 - Set 5/8" x 32" rerod with cap and set carsonite marker post.  
 Witness: Set nail in 4" Jack Pine N 38° W 5.52'  
 Set nail in 4" Jack Pine N 79° E 18.44'  
 Set nail in 6" Jack Pine S 36° E 6.03'  
 Set nail in 4" Jack Pine S 43° W 17.64'

Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 8-18-98

