

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Roscommon (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	T _____ R _____	_____
	S <u>7</u> T <u>24N</u> R <u>2W</u>	<u>8</u>
	S <u>7</u> T <u>24N</u> R <u>2W</u>	<u>11</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on July 25, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

8- This corner position was not established during the original government survey.

11- This corner position was not established during the original government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

8- Established the Northwest corner of the Northeast quarter of the Southwest quarter of section 7 as per B.L.M. instruction for subdivision of a section.

11- Established the Southwest corner of the Northeast quarter of the Southwest quarter of section 7 as per B.L.M. instruction for subdivision of section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8- Set 5/8" X 32" rerod with P.S. cap #33981

Wit: East sign post	N25°W	10.29'
5" White Pine	N86°E	23.90'
7" White Pine	S63°W	65.08'
Fd. Conc. Mon.	N47°W	5.07'

11- Set 5/8" X 32" rerod with P.S. cap #33981

Wit: 7" W. Pine	N15°W	15.89'
4" Maple	N55°E	28.28'
3" Maple	S55°E	7.07'
Fd. Conc. Mon.	S81°E	5.40'

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 8-15-02

