

6

W pine 18 N 22 1/2 E 39

Y pine 12 N 46 W 35

West
5.50

South side section 33
over lake set post on west margin

Maple 8 N 61 W 40

Lamerack 10 S 30 1/2 W 29

18.00

Leave ~~camp~~ Lamerack swamp C.N.N.W.

25.90

Y pine 12"

40.00

W pine 14"

Quarter sec. corner.

58.09

Y pine 13"

80.00

Set post - cor. sec. 32 & 33.

W pine 14 N 68 E 20

Do. 14 N 73 1/2 W 21

West

22.68

South side sec. 34

40.00

Lamerack 10"

Set quarter sec. post.

Spruce 8 N 41 E 22

Birch 9 N 24 W 06

42.17

Intersect East-margin of lake

W pine 8"

80.00

Cor. section 33 & 34 in lake

HIGGINS LAKE

SECS 4 + 33-

(1/4 COR ON TOWN LINE)

Found 1/2 iron rod. Set by Mr. Bennett
in heart of old wood stake as estab-
lished by Newman, Co. Surveyor.

Also found 3 iron stakes 33' E
W + N - on N. E Cor, N. W Cor, S. W Cor
of cross roads.

S 1/4 33

T 24 N, R 3 W