

FEB 18 1994

9235

COMMISSION

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

Dec 28 10 27 AM '93

Robert J. ...
REGISTERED

For corners in

| Roscommon (County) | Located in: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 24N R 3W | A - 7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93**

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Marvin E. Myers, in a field survey on Dec, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|--|--|---|--|
| GLO - April 1839 J.Brinks Mon. - Post WIT: 9" B.Oak S03°W 44 lks. 24" W.Pine N81°W 25 lks. | May 1940 G.Delmater Mon. - 1/2"x24" Bar Fd. GLO & BTS WIT: 10" W.Oak N74°E 75.20' 12" W.Oak N75°W 71.00' | Consumers Power Company Mon. - 1/2" Rod WIT: P.P. West 28.20' Plat Mon. N80°E 33.90' 12" W.Oak N74°E 75.20' 14" W.Oak N75°W 71.00' | L.3 P.11 Huntington Shores July 1946 by G.F.Delmater Mon- Not given. Dec 1901 L 1, P 16 by A.E. Newman Mon- Not given |
| GLO - June 1852 W.Burt Mon. - fd. Post noted above WIT: 14" Y.Pine S41 1/2°E 55 lks. | Reg. of Deeds Nov. 1945 R.Ostling & G.Henning Mon. - 1/2" Bar WIT: 10" W.Oak N74°E 75.20' 12" W.Oak N75°W 71.00' | Aug 1946 L 3, P 4 FAIRVIEW by G. Henning Mon- Not given | |
| Pg. 15 Co. Survey Records G.Delmater Dec. 1929 Mon. - Iron WIT: 30" W.Pine N25°W 47.00' 6" B.Oak N53°E 37.00' 14" B.Oak S41°W 15.00' (fd. 2 GLO BT's & post) | L.2, pg. 522 Reg. of Deeds Mon. - 1/2" Bar WIT: P.P. West 28.20' Plat Mon. N80°E 33.90' 12" W.Oak N74°E 75.20' 14" W.Oak N75°W 71.00' | Sept 1971 ELLIXSON ESTATES by L. Cavanagh L 7. P 3 Mon- 1/2" bar | Oct 28, 1924 G.F. DelaMater Mon- Iron at Corner Wit- 30" W. Pine N24W 47 6" B. Oak N53°E 37 14" B. Oak S41°W 5 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner. Found 1/2" x 36" bar alongside 1/2"x47" bar with stone pile around the bars 25'± North of center line of County Road #200 and accepted as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon- Set in exact location Standard Roscommon County 2"x21" Monument.
Wit- Plat Concrete monument N82°E 34.02
Set nail & tag NE side 21" W. Oak N66°W 71.36
Nail and tag S. side Power Pole N83°W 26.54
Set nail & tag NW side 15" W.Oak N81°E 72.81
Set nail & tag NE side 15" W. Oak S39°E 86.46
Found RR spike in centerline of Road intersection S06°W 26.65
E edge of E. post of Ped. Sign N20°E 55.10



Signed by *Marvin E. Myers*

Date Dec 21, 1993

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

DATE Dec 14, 1993 PEER GROUP APPROVAL

LIBER

3 PAGE 61